SCHEDULE 4

THE A20 IMPROVEMENT WORKS

PART I

THE AUTHORISED WORKS

Description of works

The works which the Secretary of State is authorised by section 35 of this Act to construct are the following—

In the district of Dover (town of Dover and parishes of Capel-le-Ferne and Hougham Without) and the district of Shepway (town of Folkestone and parish of Hawkinge), in the county of Kent—

Work No. 31—A road forming the northern carriageway of a dual carriageway road, including a viaduct, commencing by a junction with the northern carriageway of the M20 at a point 90 metres west of the underpass whereby the footpath from Elvington Road to Biggins Wood Road passes under the M20, passing east and turning north-east over land known as Holywell Coombe by means of the viaduct, then in tunnel under Round Hill and Crete Road West (Pilgrims Way) and terminating on the west side of Canterbury Road (A260) at a point 55 metres north-west of the junction of that road with Alkham Valley Road (B2060):

Work No. 32—A road forming the southern carriageway of the said dual carriageway road, including a viaduct, commencing by a junction with the southern carriageway of the M20 at the said point 90 metres west of the said underpass, passing east and turning north-east over the said land known as Holywell Coombe by means of the viaduct, then in tunnel under Round Hill and Crete Road West (Pilgrims Way) and terminating at a point 45 metres northwest of the junction of Canterbury Road with Alkham Valley Road:

Work No. 33—A road comprising dual carriageways, commencing by junctions with Works Nos. 31 and 32 at their termination, passing north-east under Canterbury Road at a point 50 metres north of its junction with Alkham Valley Road, then along a line to the north of Alkham Valley Road, then crossing over that road by a bridge at a point 125 metres north-west of the entrance to Havenfield Lodge, then passing east, crossing under Cauldham Lane, Capel Street and Satmar Lane, then turning south-east and terminating at a roundabout forming a junction with the A20 (Works Nos. 44A and 44B) at a point 480 metres south-west of the entrance from that road to Court Wood:

Work No. 34—A grade separated junction comprising—

Work No. 34A—A slip road commencing by a junction with Work No. 31 at a point 220 metres from its commencement and terminating at the entry to a northern junction roundabout (part of Work No. 34C) at a point 80 metres north of the northern end of the bridge carrying the M20 over Waterworks Lane;

Work No. 34B—A slip road commencing at the exit from the said northern junction roundabout and terminating by a junction with Work No. 31 at a point 280 metres east of the existing junction of Castle Hill with the Castle Hill Roundabout;

Work No. 34C—A road, including junction roundabouts at its commencement and termination and a bridge over Works Nos. 31 and 32, commencing at the said northern junction roundabout at the termination of Work No. 34A and terminating at a southern junction roundabout at a point 85 metres south of the said existing junction of Castle Hill with the Castle Hill Roundabout;

Work No. 34D—A realignment and alteration of the southern carriageway of the M20 to form a slip road, commencing at a point in the said carriageway 270 metres west of the southern end of the said bridge carrying the M20 over Waterworks Lane and terminating at the exit from the said southern junction roundabout;

Work No. 34E—A slip road commencing at the entry to the said southern junction roundabout and terminating by a junction with Work No. 32 at a point 400 metres east of the said existing junction of Castle Hill with the Castle Hill Roundabout;

Work No. 34F—A road in substitution for part of Churchill Avenue commencing by a junction with the said southern junction roundabout and terminating by a junction with the southern carriageway of Churchill Avenue at a point 440 metres east of that roundabout;

Work No. 34G—A realignment of Cherry Garden Avenue, commencing at the said southern junction roundabout and terminating at the junction of that road with Papworth Close;

Work No. 34H—A road in substitution for part of Castle Hill at its junction with the Castle Hill Roundabout, commencing by a junction with that road at a point 260 metres north of that roundabout, passing southwest and west and terminating at the northern junction roundabout at the termination of Work No. 34A:

Work No. 35—A diversion and extension of Park Farm Road, commencing by a junction with Work No. 34F at a point 150 metres west of the termination of that work and terminating at a point in Park Farm Road 75 metres from its commencement:

Work No. 36—A widening on the north side of Crete Road West (Pilgrims Way) between its junction with Gibraltar Lane and its junction with Canterbury Road at a point 235 metres south of the junction of that road with Alkham Valley Road:

Work No. 37—A realignment of Canterbury Road and regrading of its junction with Alkham Valley Road, including a bridge over Works Nos. 33, 38A and 38C, commencing at a point in Canterbury Road 420 metres north of that road junction as existing and terminating at a point 250 metres south of that road junction:

Work No. 38—Junctions of Works Nos. 31, 32 and 33 with Canterbury Road and Alkham Valley Road comprising—

Work No. 38A—A slip road commencing by a junction with Work No. 31 at a point 190 metres south-west of the termination of that work, passing under Canterbury Road and turning north and west to terminate at a roundabout forming a junction with that road at a point 240 metres north of its junction with Alkham Valley Road;

Work No. 38B—A slip road commencing at the said roundabout forming a junction with Canterbury Road at the termination of Work No. 38A and terminating by a junction with the northern carriageway of Work No. 33

at a point 385 metres south-west of the existing junction of Church Hill with Alkham Valley Road;

Work No. 38C—A slip road commencing by a junction with Work No. 32 at a point 80 metres south-west of the termination of that work, passing under Canterbury Road and terminating at a roundabout forming a junction with Alkham Valley Road at a point 340 metres from its junction with Canterbury Road;

Work No. 38D—A slip road commencing at the said roundabout forming a junction with Alkham Valley Road at the termination of Work No. 38C and terminating by a junction with the southern carriageway of Work No. 33 at a point 220 metres south-west of the said existing junction of Church Hill with Alkham Valley Road:

Work No. 39—A road, including a bridge over Works Nos. 33 and 38D, in substitution for part of Church Hill at its junction with Alkham Valley Road, commencing by a junction with Alkham Valley Road at a point 100 metres north-east of the existing entrance to Coombe Farm, passing north, then turning north-east and terminating at a point in Church Hill 100 metres from the existing junction of that road with Alkham Valley Road:

Work No. 40—A road in substitution for part of Crete Road East at its junction with Alkham Valley Road, commencing by a junction with Alkham Valley Road at a point 30 metres east of the existing entrance to Havenfield Lodge and terminating at a point in Crete Road East 15 metres south-west of the entrance to Havenfield Hall:

Work No. 41—A diversion of Cauldham Lane, including a bridge over Work No. 33, commencing at a point in that road 125 metres south of its junction with the road to Lower Stenden Farm and terminating at a point in Cauldham Lane at its junction with Hurst Lane:

Work No. 42—A realignment and regrading of Capel Street, including a bridge over Work No. 33, commencing at a point in that road 150 metres south-west of its junction with Satmar Lane and terminating at a point in Capel Street 180 metres north of its junction with Hurst Lane:

Work No. 43—A diversion of Satmar Lane, including a bridge over Work No. 33, commencing at a point in that road 560 metres south-west of its junction with Crook's Court Lane and terminating at a point in Satmar Lane 300 metres north-east of Ivy Farm:

Work No. 44—A junction of Work No. 33 with the A20 at Court Wood comprising—

Work No. 44A—A diversion of the A20 as existing, commencing at a point in that road 310 metres east of the existing entrance to Abbots Land Farm and terminating at the said roundabout at the termination of Work No. 33;

Work No. 44B—A diversion of the A20 as existing, commencing at the said roundabout at the termination of Work No. 33 and terminating at a point in the A20 95 metres west of the entrance to Court Wood.

Limits of deviation

2 In their construction—

(a) each of the works described in paragraph 1 above may deviate from the line or situation shown for that work on the deposited plans to the extent of the limits of deviation so shown;

- (b) so much of each of Works Nos. 31 and 32 as lies between its commencement and the point at which it passes into tunnel under Round Hill may deviate from the level shown for that part of that work on the deposited sections to the extent of 1.5 metres upwards and to any extent downwards; and
- (c) each of the works described in paragraph 1 above, other than the parts of Works Nos. 31 and 32 specified in sub-paragraph (b) above, may deviate from the level shown for that work or, in the case of Works Nos. 31 and 32, that part of that work on the deposited sections to the extent of 3 metres upwards and to any extent downwards.

Interpretation of Part I

In paragraph 1 above, "A20" means the trunk road from Folkestone to Dover so classified.

Changes to legislation:

There are currently no known outstanding effects for the Channel Tunnel Act 1987, Part I.